OFFICE OF THE SUPERINTENDENT, HILL STATIONS IN MYSORE, LAL-BAGH, BANGALORE.

Notice is hereby given that sealed tenders will be received at the Office of the Superintendent, Hill Stations, Lal-Bagh, Bangalore, up to 3 P.M. on *27th March* 1931, for repairs to be done to Bungalows in the Nandi Hill Station up to the end of June 1932. An approximate quantities of work to be done are given below. These quantities are not guaranteed.

2. Tenders should be submitted on printed forms (which may be obtained from the office of the undersigned) showing the rates at which different items specified will be executed.

3. Each tender must be accompanied by a deposit of Rupees one hundred, in cash as earnest money and it should be superscribed "Tender for building repairs to, in Nandi Hill Station," in default of which, tenders will be rejected.

4. The final acceptance of any tender will rest with the Director of Horticulture, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

5. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited to Government.

6. The successful competitor whose tender has been accepted will be informed in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

8. Rates should be quoted for each item of work.

9. Percentage rates either below the estimated amount or the lowest tender will not be accepted.

10. In the case of non-tendered items the rates will be given after striking the data for which the tenderers should accept.

11. No claim for enhanced rates should be preferred at any time during the course of the period.

12. In all matters of dispute regarding quality of work or rates, etc., the decision of the Director of Horticulture is final.

Abstract of the approximate quantities of repair works to be done to Government Bungalows in the Nandi Hill Station.

No.	Items of work	Unit	Quantity	Rate
				Rs.
1	Two coats whitewash after repairing cracks, holes, etc., in chunam.	Sqr.	400	
2	Two coats distemper or Calcarium wash after repairing cracks, holes, etc., in chunam.	,,	200	
3	Two coats cement wash after repairing the cracks, holes, etc., in chunam.	,,	200	
4	Two coats colour wash after repairing the holes and cracks, etc., in chunam.	,,	200	
5	Two coats of Cilicate paint after cleaning the old paint.	,,	100	
6	Renewing glass panes 3/10″ thick	Sq.ft.	100	
7	Iron hooks 3″	Each	50	
8	Do 6″	,,	50	
9	Do 9″	,,	50	
10	Do 1′	,,	50	
11	Tower bolts of sizes	Each inch	500	
12	Chunam plastering	Sqr.	50	
13	Chunam painting	,,	50	
14	Teakwood wrought and put up	C.ft.	50	
15	Do windows with iron bars, etc.	S.ft.	200	
16	Do doors with panel shutters complete of ½″ thickness.	Sq.ft.	200	
17	Burnt brick in mud	C.ft.	200	
18	Burnt brick in chunam	,,	200	
	Stone work in mud	...	200	
	Stone work in chunam	...	200	
19	Stone slabs including 2 line dressing and fixing in chunam and cement painting.	Sq.ft.	200	
20	Cuddapah slab flooring on 3″ concrete including cement painting complete.	Sqr.	20	
21	Flooring with 1st Class Mangalore clay tiles on 3″ concrete and cement painting complete.	,,	20	